INSTALLATION GUIDE

Tower Maxi T UPS

Single phase input – single phase output

Single conversion on line UPS





17 Fennel Street, Village Deep, Johannesburg. PO Box 3274, Northcliff 2125 <u>Tel: 011 4935889 011 493 5721 Fax: 011 4936479</u>

INSTALLATION

GENERAL

The following information will be of assistance when installing your UPS. Care should be taken to select the correct circuit breakers and cable sizes. Information is provided in the table below that will assist with the selection.


INPUT AND OUTPUT CABLING AND CIRCUIT BREAKER DATA

The recommended input circuit breaker (in clients' DB board) and cable sizes for the different UPS units are as follows:

NOTE:

- The input circuit breaker must have a D curve rating.
- All cable sizes are rated for a maximum distance of up to 50 meters.


UPS Rating (kVA)	Input Current	Recommended Circuit Breaker	Recommended Input Cable	Output Current	Recommended Output Cable
5	22A	30A 1 pole	6mm ² 2c+e	22A	4mm ² 2c+e
8	35A	40A 1 pole	10mm ² 2c+e	35A	6mm ² 2c+e
10	44A	50A 1plole	10mm ² 2c+e	44A	10mm ² 2c+e
15	67A	80A 1 pole	16mm ² 2c+e	65A	16mm ² 2c+e
20	87A	100A 1 pole	20mm ² 2c+e	87A	20mm ² 2c+e




BATTERY CONNECTION

A battery tray can house 16 batteries.


[32 batteries per bank.]






Connect the short interconnecting cables (indicated in **red**) to all the batteries on the LHS and RHS.

Leave the 2 links at the back of the tray open (indicated in green), theses battery links will later be connected using the longer links.






LAST BATTERY LINK (Green)

Once all the wires are secure in the fuse holders, and you are ready to carry on, slightly open each battery tray and measure the differential between the last two battery terminals (ie the two that do not have any wires connected to them)

If this differential voltage is less than 3VDC, it is safe to insert the medium end connector cables across those links that were just measured (Green).

Take care when re-closing the trays that these medium connecting cables are tucked under the above tray to avoid them being pinched.



SYSTEM OPERATING PROCEDURES

INITIAL STARTUP OF UPS UNIT

- Turn the INVERTER KEY SWITCH to the off position.
 - For 5kVA and 8kVA units
 - Place the ROTARY BYPASS switch into the TEST position.
 - For 10 20kVA units
 - Close the BYPASS ISOLATOR (SW2).
 - Open the OUTPUT ISOLATOR (SW1).
- Close the AC input circuit breaker (CB1).
- The LCD will activate.
- After a period of approximately 30 seconds the analog values and status alarms will be displayed.
- The unit will synchronise to mains.
- Depress ALARM CANCEL button to silence alarm.
- Turn the INVERTER KEY SWITCH to the "ON" position.
- The unit will start up within 10 20 seconds.
- The UPS output voltage will ramp up to 230VAC.
- Ensure that *NO ACTIVE ALARMS* is displayed in the alarm status block and that the battery voltage is greater than 360VDC (432VDC is the charging value).
- Measure the DC differential voltage across (from top to bottom of...) F1 (with the multimeter set to DC).
 Close ONLY THIS FUSE if the differential voltage is less than 30VDC.
- Repeat for F2 and F3.
- Turn the INVERTER KEY SWITCH to the "OFF" position and confirm LOAD ON BYPASS is displayed on the LCD DISPLAY.
 - For 5 8kVA units
 - Place the ROTARY BYPASS switch into the NORMAL position.
 - For 10 20kVA units
 - Close the OUTPUT ISOLATOR (SW1).
 - Open the BYPASS ISOLATOR (SW2).
- Turn the *INVERTER KEY SWITCH* to the "ON" position (CW) and depress *ALARM CANCEL* button to silence alarm.
- Confirm *NO ACTIVE ALARMS* is displayed on the LCD DISPLAY within 60 sec.
- The unit is operating normally.

SHUTING THE UNIT DOWN – (without loosing power to the load)

- To transfer to bypass without loosing the load, ensure that *NO ACTIVE ALARMS* is displayed.
- Turn the INVERTER KEY SWITCH to the off position. The load is now supplied by mains via the static switch. Confirm LOAD ON BYPASS is displayed.
 - For 5 8kVA units
 - Place the ROTARY BYPASS switch into the TEST position.
 - For 10 20kVA units
 - Close the BYPASS ISOLATOR (SW2).
 - Open the OUTPUT ISOLATOR (SW1).
- The load is now supplied by mains via the detour (bypass) switch.
- Open DC Input fuses (F1,F2 andF3).
- Open AC input circuit breaker (CB1).
- Wait 1 min for the internal capacitors to discharge (Electronics will die when discharged.)
- To switch the unit on again, refer to INITIAL STARTUP.